

9 May 2007

Company Announcements Office Australian Stock Exchange Limited

Via ASX Online

Dear Sirs,

OPERATIONS UPDATE THAILAND

Na Sanun-3 Appraisal Well

The Na Sanun-3 appraisal well, located on the southern most limb of the 3.1 square kilometre Na Sanun structure (see attached figures), was drilled and cased to a total depth of 1,060 metres on April 24, 2007. The target volcanic reservoir was encountered at a depth of 961 metres over an interval of approximately 77 metres thick with oil shows encountered over the upper 20 metres. Subsequent testing over a gross interval of approximately 62 metres (961 metres to 1023 metres) resulted in water production at rates of approximately 75 barrels per day with traces of oil and gas. Testing operations of Na Sanun-3 continue and will likely include the setting of a bridge plug in an attempt to isolate water which may be originating from the deepest set of perforations. Material results will continue to be reported as they are available.

Na Sanun-4 Appraisal Well

At the Na Sanun-4 appraisal well, located approximately midway between Na Sanun-1 and Na Sanun-3 (see attached figures), intermediate casing has been set and the well is being drilled ahead from the current depth of approximately 800 metres. Five potential volcanic reservoir intervals are targeted, all of which are interpreted to be at the shallowest depth on the Na Sanun structure at this location. The planned total depth of 1,400 metres, including the cutting of one core, is expected to be reached in approximately 8 days.

Telephone +61 8 9321 2665

Facsimile +61 8 9321 8867

e-mail: admin@carnarvonpetroleum.com

Yours faithfully,

Carnarvon Petroleum Limited

RA Anderson

Company Secretary



